

7011.1135 PERFORMANCE TEST PROCEDURES.

Subpart 1. **In general.** Performance tests must be conducted according to the requirements of this part and parts 7017.2001 to 7017.2060.

Subp. 2. **Special procedures.** For Method 5, the sampling time for each run must be at least 60 minutes and the minimum sampling volume must be 0.85 dscm (30 dscf) except that owners or operators may, prior to testing, request approval from the commissioner for smaller sampling times or volumes, when necessitated by process variables or site-specific limitations. Sampling must not be started until at least 30 minutes after start-up and must be terminated before shutdown procedures commence. The owner or operator must eliminate cyclonic flow during performance tests.

Statutory Authority: *MS s 115.03; 116.07*

History: *L 1987 c 186 s 15; 18 SR 614; 18 SR 1412; 41 SR 763*

Published Electronically: *January 27, 2017*